

Tile Roof Installation

Gumleaf Gutter Protection is one of the leading companies in New Zealand

Tile Roof Installation

Our process for measuring your Gutter

- ✓ Step 1: We measure the length of the guttering and add 5-10% for overlap and wastage.
- ✓ Step 2: Measure the gap between gutter lip and edge of tiles (this is classed as the Fold). i.e. 70-100mm. IMPORTANT: We check that the bottom row of tiles can be slid back (no cyclone clips or nails)
- ✓ Step 3: We cover any questions you may have, then we offer a no-obligation quote.
- ✓ Step 4: On acceptance of our quote, we work on a 7 to 10 day period to begin your guttering installation. Completion of the installation is usually one to two days, dependent on the size of your home.

Installation of Gutterguard

Our process for Tile Roof Gutterguard

Step 1

- ✓ Our installer cleans out the gutters and flushes the down-pipes.




Step 2

- ✓ The tiles are then slid back to original the position.



Step 3

- ✓ Screws are placed into gutter lip approximately 300mm apart.



Step 4

- ✓ We then fold down the back piece to create a double fold.




Step 5

- ✓ The first row of tiles back is then slid back into position.



Step 6

- ✓ Cutting is then carried out to the desired length of the corner.



Step 7

- ✓ The Overlap guard is approximately 10mm.



Step 8

- ✓ The Interlock guard placed in middle of both pieces.



Step 9

- ✓ We cut and screw it neatly to fit comfortably into the corner



Step 10

- ✓ Screw corner piece down.

